



ITEM NO.	DESCRIPTION	EST. QNTY.	UNIT	UNIT PRICE	TOTAL PRICE
004-2022 Unity Park Road Iprovement Project ADDENDUM NO. 2					
General Project					
1-1	Mobilization, Bonds and Insurance (not to exceed 3% of Total Bid) and project signage.	LS	1		
1-2	Traffic control plan signed and sealed by a professional engineer licensed in Texas	LS	1		
1-3	Installation and maintenance of barricades, signs and traffic handling per approved Traffic Control Plan.	LS	1		
Total General Project				\$	-
BASE BID - Unity Park Road Improvements Project					
2-1	Place 3-inch Hot Mix Asphalt Concrete Type "D" (3-inch compacted thickness) according to the plans and specifications; complete in place.	SY	1343		
2-2	Prime Coat (MC-30) (0.2 GAL/SY), according to the plans and specifications; complete in place.	GAL	270		
2-3	8-inch Caliche Base (8-inch compacted thickness) according to the plans and specifications; complete in place.	SY	1490		
2-4	6-inch Lime treated Sub-Grade (4 % dry weight) according to the plans and specifications; complete in place.	SY	1490		
2-5	Furnish and Install 5-ft Concrete Flume with headwall & diffusers composed of large potato rock or equal	EA	1		
2-6	3-inch Commercial Driveway Asphaltic Pavement connecting to FM 508, according to the plans and specifications; complete in place	LS	1		
2-7	Furnish and Install 18-inch RCP Culvert for Driveway with Wingwall; according to the plans and specifications; complete in place	LF	52		
2-8	Furnish and Install 18-inch RCP according to the plans and specifications; complete in place	LF	77		
2-9	Furnish and install two (2) curb inlets per plans and specifications; complete in place	EA	2		
2-10	Furnish and install 4" curb and gutter as per plans and specifications; complete in place	LF	906		

ITEM NO.	DESCRIPTION	EST. QNTY.	UNIT	UNIT PRICE	TOTAL PRICE
004-2022 Unity Park Road Improvement Project ADDENDUM NO. 2					
2-11	Furnish and install two (2) Type III Barricades as per plans and specifications; complete in place	EA	2		
2-12	Installation of 24" Steel Casing; wet connection; with skids, for existing 18" PVC Irrigation Line; complete in place	LF	40		
2-13	Furnish and Install Storm Discharge Structure according to the plans and specifications; complete in place	EA	1		
2-14	Installation and grading of ditches as per plans and specifications; complete in place	LS	1		
2-15	Excavate and fill of proposed road at no extra pay; to be included in pricing of proposed construction of new road. This includes any and all materials to elevate road and other proposed structures to insure proper elevations.	LS	1	No Extra Pay	No Extra Pay
2-16	Diversionary pumping and or dewatering to be included in project at no extra pay and should be included in pricing for selected items.	LS	1	No Extra Pay	No Extra Pay
2-17	installation of TxDot approved "Stop" sign to a height required by plans and specifications; complete in place.	LS	1		
2-18	Road and Pavemet marking required by Uniform Traffic Manual; approved TxDOT paint; dimensions, complete in place.	LS	1		
Unity Park Road Project					
TOTAL GENERAL PROJECT					
UNITY PARK ROAD PROJECT					
TOTAL PROJECT					



2-4-22

A handwritten signature in blue ink, appearing to read "All [unclear]".